



NOTES:

- ① WC, 1/2" CW
- ② L, SH, 1/2" CHW
- ③ KS/DW, 1/2" CHW
- ④ 1/2" CW TO REF. ICEMAKER WATER BOX.
- ⑤ PROVIDE LINE SIZED SHUT-OFF VALVE, PRESSURE REGULATOR SET TO 80 PSI AND BACKFLOW PREVENTER IN CONCRETE YARD BOX AT CURB.
- ⑥ 1/2" CHW TO CLOTHES WASHER BOX.
- ⑦ 3/4" CHW TO GAS TANKLESS WATER HEATER.
- ⑧ ROUTE PRESSURE RELIEF LINE FULL SIZED TO THE OUTSIDE LANDSCAPE OR TO A CODE APPROVED LOCATION WITH 6" AIR GAP.
- ⑨ ROUTE 1/2" CHW DOWN IN WALL, THEN IN PONY WALL OVER TO KS.
- ⑩ 1" CW, ROUTE TO LOWER AND UPPER LEVELS.
- ⑪ 1" CW, ROUTE UP TO CEILING SPACE.
- ⑫ 1/2" CW TO HB, WITH VACUUM BREAKER.
- ⑬ CONTINUATION TO EXISTING CITY WATER SYSTEM. REFER TO CIVIL UTILITY SITE PLAN FOR EXACT LOCATION.
- ⑭ GAS METER BUILDING (A):
2" G, MAIN TOTAL LOAD OF 1036 CFH AND A TOTAL DEVELOPED LENGTH OF 86 FT. (90 FT. ROW) PER UPC TABLE 1216.2(1), 2012 UPC.
- ⑮ GAS METER BUILDING (B):
1 1/2" G, MAIN TOTAL LOAD OF 548 CFH AND A TOTAL DEVELOPED LENGTH OF 61 FT. (110 FT. ROW) PER UPC TABLE 1216.2(1), 2012 UPC.
- ⑯ PROVIDE LINE SIZED SHUT-OFF VALVE TO BUILDING.
- ⑰ 3/4" G, ROUTE DOWN IN WALL, THEN IN PONY WALL OVER TO RANGE.

REVISED ENTIRE SHEET
2-25-19

NORTH

FIRST FLOOR - PLUMBING PLAN (WATER & GAS)
 SCALE: 1/4" = 1'-0"

NO.	DATE	DESCRIPTION	BY
1	2-25-19	BUDGET COMMENT	
2	2-25-19	OWNER REVIEW	



7010 Easy Wind Dr. Ste 200
Austin, TX 78752
512.899.3100

www.designopa.com



51 E. TEXAS AVE.
HENDERSON, NEVADA

JOB NO.:	201724-A
PHASE:	CD
DRAWN:	SO, LE
CHECKED:	SO
DATE:	10/22/2018

P101.1